MATERIALS SCHEDULE

For The Proposed Development At:

Land Rear of Barker Cottages New Cut, Dean Street East Farleigh Kent ME15 0HR

PL / 444 / 17 Rev B

Rev A – brick choice updated 12/06/2019
Rev B – brick for herringbone panels & brick quoins updated 08/08/2019

Andrew Wells Architectural Planning and Design Ltd.

Hollywood House, 76 Hollywood Lane Wainscott, Rochester Kent ME3 8AR

Tel: 01634 786728 Mob: 07535 621806 E-mail: andy@wellsdesign.co.uk

May 2019

MATERIALS SCHEDULE - NEW HOUSE

Facing Bricks: Ibstock Leicester Weathered Multi

Herringbone Panels &

Brick Quoins:

Reclaimed Kent red bricks

Limestone: Reclaimed limestone found on site

Infill Walling: Spaced oak columns on stone

plinths

Mortar: Cement / lime mortar

Roof Tiles: Primera Elapi slate

Windows: Double glazed white painted timber

Entry Doors & Bifold Doors: White painted timber

Rainwater Goods: Black cast iron style of traditional

section

Private Footpath & Driveway: Angular limestone chippings laid

over consolidated hardcore